

**Evan Smith from Patriot Construction Management has a message
regarding the project Everett WA P&DF/North DDC**

BID PACKAGE NAME

Everett WA SDC - Phase 1

**ADDENDUM #2 - CODED NOTE #1 ON A-100 AND A 201 REVISED AS
INCLUDED**

Coded Note #1 on A-100 and A-201 needs to be revised as follows:

1. EXTERIOR BUILDING WORK TYPICAL ALL SIDES OF BUILDING:
 - PRESSURE WASH ALL EXTERIOR SURFACES
 - PATCH, REPAIR, AND RE-PAINT ALL PREVIOUSLY PAINTED SURFACES. COLOR AND STYLE TO MATCH EXISTING

CONSTRUCTION.

- REMOVE OLD SEALANT AND BACKER RODS, INCLUDING ALL WINDOWS AND DOORS. DO NOT CAULK

OVER EXISTING WEEP HOLES. INSTALL NEW BACKER ROD AND SEALANT INPLACE TO MATCH EXISTING

COLOR.

- ALL PREVIOUSLY PAINTED METAL SURFACES TO BE SCRAPED AND REPAINTED TO MATCH EXISTING

PAINT COLOR. VERIFY COLOR IN FIELD. INCLUDED BUT NOT LIMITED TO PREVIOUSLY PAINTED

BOLLARDS, GUARD RAILS, METAL DOORS AND FRAMES ETC.

The drawing package had the brick building note included (tuckpointing), instead of the painted building note.

We will revise and reissue these two sheets

Powered by:

Procore Technologies Inc.

6309 Carpinteria Ave, Carpinteria, CA 93013

support@procore.com