

Pacific Region Lynwood Washington  
New Generation Delivery Vehicle (NGDV)  
Vehicle Maintenance Facility (VMF)  
RFP No.: 30902332.02191R  
USPS Project No.: E09779

Contract No.: 104267-21-B-0030

WSP-Korte Project No. 30902332.02191

**Addendum No. 2**

To: All Bidders  
From: WSP-Korte,  
Subject: **RFP 30902332.02191**  
Re: **Lynwood (North)**  
**NGDV VMF Upgrades**

Dear Bidders,

The changes found within are hereby made effective as though originally issued with the RFP BidPackage. All other subjects remain the same.

**Addendum No. 2**

**Technical Section**

**1. Technical**

a. **Questions received with Answers: RFI Log dated, 2.2.2024.**

**2. Contracts and Procurement Section**

a. **Questions Received with Answers: None**

**3. Documents in Amendment Folder (7 total):**

- a) **Addendum No.2 RFP 30902332.02191 (This Document)**
- b) **RFI Log dated 2.2.2024.**
- c) **Design Rev1 Summary**
- d) **Design Rev1 Arch**
- e) **Design Rev1 Elect**
- f) **Design Rev1 Civil**
- g) **Specs Rev1**

\*\*\*\*\*

\*\*\*\* Each Bidder must acknowledge receipt and acceptance of this addendum by close of business (COB) – 2/6/2024. Email to [wspkorteuspsrfp@wsp.com](mailto:wspkorteuspsrfp@wsp.com). **Must include RFP # Name of Project in Subject line.**

**Hilger Construction, Inc.**

Name of Company: \_\_\_\_\_

Authorized Signature: David Mack

**David Mack, VP**

Print Name and Title: \_\_\_\_\_

Request for Information (RFI)	Project	USPS SharePoint Addendum	Bidder	Bidder, POC	Question	Answer
RFI 1	Lynnwood VMF Project		Happel	Andrew Royappa	Stonhard has informed us that the Stonglaze VSR product specified is intended for application on walls, not floors. Could you please verify what floor coating product is to be used?	<b>Spec has been revised. See Spec Section 096723 - Resinous Flooring</b>
RFI 2	Lynnwood VMF Project		Happel	Andrew Royappa	1. Could you please specify the red highlighted dimension for the rack detail 11, sheet C500?  Do we have asbestos survey on this building. We were notified!	<b>Dimension shown to be 6".</b>
RFI 3	Lynnwood VMF Project		Happel	Andrew Royappa	1. Detail 1 on sheet C500 specifies a concrete wheel stop, but the specs call for a recycled plastic parking block. Could you please clarify which is to be used?	<b>Concrete wheel stops to be installed.</b>
RFI 4	Lynnwood VMF Project		Saybr	Terry Griffin	The site immediately asked if we are upgrading restrooms. Who can we refer the site manager to about these items not in our scope?	<b>Restrooms are currently not in scope. WSP will follow up with RA facilities manager.</b>
RFI 5	Lynnwood VMF Project		Saybr	Terry Griffin	Do we have asbestos survey on this building. We were notified by the site that they have known hot spots.	<b>Please provide an allowance, and provide note on assumption to quantify value provided.</b>
RFI 6	Lynnwood VMF Project		Saybr	Terry Griffin	Note 24 on G002 states to Paint existing lower bumpers and to install new upper bumpers. Please provide additional detail.	<b>Note does not apply and has been removed from G002.</b>
RFI 7	Lynnwood VMF Project		Saybr	Terry Griffin	Note 26 on G002 states all wall, door and ceiling signage to be replaced. Please provide additional detail.	<b>Note does not apply and has been removed from G002.</b>
RFI 8	Lynnwood VMF Project		Saybr	Terry Griffin	Can we get additional specs on lifts installed by others so we can fully understand scope of our "prep work"	<b>Additional specs are not available. Patch and repair floor to prepare for new lifts. All fixtures and mechanical systems within existing service areas of lifts at or below 15'-3" A.F.F. shall be relocated above 15'-3" A.F.F.</b>
RFI 9	Lynnwood VMF Project		Saybr	Terry Griffin	Per drawing notes, all lifts are to be removed and installed by others. GC is only responsible for floor prep. Please verify.	<b>Floor prep and all fixtures and mechanical systems within existing service areas of lifts at or below 15'-3" A.F.F. shall be relocated above 15'-3" A.F.F.</b>
RFI 10	Lynnwood VMF Project					

